

ACO-1 (Cont.)

SMITH ESTATE #5-17
SW SW NE, Sec 17-21s-11w
Stafford County, KS
API# 15-185-22,718

DST #1 (3270-3310) LKC "H" - "I"

1) WB Dead in 3 mins

2) NB, Flush, WB Dead 2"

REC: 10 DM

IHP: 1624

IFP: 55-40:15"

ISIP: 59:15"

BHT: 109F

FHP: 1639

FFP: 54-51:15"

FSIP: 56:15"

DST #2 (3376-3430) CONGLOMERATE - SIMPSON SAND

1) WB Dead in 3", Flush, WB Dead 2"

2) NB

REC: 10' Slt OIL SPK MUD

IHP: 1736

IFP: 77-67:15"

ISIP: 128:45"

BHT: 111F

FHP: 1663

FFP: 85-75:15"

FSIP: 124:45"

DST #3 (3463-3478) ARBUCKLE

1) WB Dead 4", Flush, No Help

2) NB

REC: 80' DM w/TR OIL (no wtr)

IHP: 1716

IFP: 50-54:15"

ISIP: 1040:30"

BHT: 112F

FHP: 1693

FFP: 71-63:30"

FSIP: 897:30"

DST #4 (3477-3485) ARBUCKLE

1) WB Dead 10", Lost 5-10' DM Before Packer Set

2) NB, Flush, No Help

REC: 70' DM w/Show Oil on Tool

60' WTU MUD

130' Total

IHP: 1738

IFP: 68-79:15"

ISIP: 1124:30"

BHT: 113F

FHP: 1730

FFP: 111-99:15"

FSIP: 1127:30"

DST #5 (3484-3500) ARBUCKLE

1) FB 1 1/4" increasing to 8" then decreasing to 1/4" in bucket

2) WB 1/4" and dead in 14"

REC: 450' Slt O&GMW (Less than 1% Oil on top)

IHP: 1759

IFP: 51-108:30"

ISIP: 1140:60"

BHT: 111F

FHP: 1719

FFP: 163-198:30"

FSIP: 1119:60"