

APR 27  
CONFIDENTIAL

APR 15-185-22894

MEYER NO. 1-5  
900'FNL 1400'FEL  
SEC 5-21S-11W  
Stafford County, Ks.RECEIVED  
KANSAS CORPORATION COMMISSION

APR 27 1993

CONSERVATION DIVISION  
WICHITA, KSDRILL STEM TESTS

- DST 1: 3150 - 3197, 15-30-15-30  
1st Blow, Weak blow for 3 min. and died.  
2nd Blow, No blow, flushed tool, good surge, no help.  
IHP 1660 FHP 1649 IFP 89-78 ISIP 133 FFP 89-78 FSIP 122 BHT 104°  
Rec: 40' Mud with a fair show of oil between shut-in and hydrolic tools.
- DST 2: 3370 - 3400, 30-60-60-90  
1st Blow, Weak blow  
2nd Blow, Weak blow  
IHP 1726 FHP 1704 IFP 55-55 ISIP 998 FFP 66-66 FSIP invalid BHT 107°  
Rec: 450' Gas in pipe. 30' Oil cut mud. 60' Very gassy slightly muddy oil  
65% Gas 18% Oil 10% Mud 7% Water. 60' Very gassy oil cut watery mud,  
22% Gas 30% Oil 28% Mud 20% Water.
- DST 3: 3387 - 3412, 30-60-60-90  
1st Blow, Fair blow, Bottom of bucket in 12 min.  
2nd Blow, Fair blow, Bottom of bucket in 14 min.  
IHP 1760 FHP 1749 IFP 55-89 ISIP 1108 FFP 100-156 FSIP 1075 BHT 109°  
Rec: 1110' Gas in pipe. 50' Clean gassy oil. 60' Gassy muddy oil,  
12% Gas 50% Oil 38% Mud. 60' Very gassy muddy oil, 58% Gas 20% Oil 22% M  
60' Muddy slight gas cut oil, 5% Gas 45% oil 52% Mud. 60' Very gassy  
muddy oil, 75% Gas 12% Oil 13% Mud
- DST 4: 3412 - 3422, 30-60-60-90  
1st Blow, Fair blow, Bottom of bucket in 14 min.  
2nd Blow, Fair blow, Bottom of bucket in 10 min.  
IHP 1771 FHP 1715 IFP 55-66 ISIP 1020 FFP 78-89 FSIP 1108 BHT 109°  
Rec: 1110' Gas in pipe. 30' Clean gassy oil. 60' Very gassy slightly  
muddy oil, 55% Gas 25% Oil 20% Mud. 60' Very gassy slightly mud and  
water cut oil, 40% Gas 30% Oil 15% Mud 15% Water.