

10-21-11W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL CO.
Farm- Sifers "B" No. 3

SEC. 10 T. 21 R. 11W
NE SE NW
890' N. & 330' W. of Center

Total Depth. 3370
Comm. 10-16-51 Comp. 10-29-51
Shot or Treated.
Contractor. Holm Drlg. Co.
Issued. 12-15-51

County Stafford
KANSAS



CASING:
8 5/8" 319' cem. w/250 sx

Elevation. 1760 Gr.
1762 (end)
Production. Dry

Figures Indicate Bottom of Formations.

sand	180
shale, red bed & shells	205
shale & shells	320
shale, shells & red bed	480
anhydrite	495
shale & shells	1440
lime & shale	1565
lime	1660
lime & shale	2160
shale & shells	2520
lime & shale	2805
lime	2860
lime & shale	3074
lime	3339
shale & sand	3345
cored shaly dolo. rec. 1 1/2'	3349
cored shaly dolo. rec. 9"	3354
lime	3370
Total Depth	

Tops:
Douglas Sand 3019
Lansing 3074
Simpson Shale 3325
Arbuckle 3340

Penetration 30'
DST: 3150-62', open 30 mins.
rec. 30' muddy salt wtr; 15 min.
B.H.P. 950#.
DST: 3341-45'; packer failed.
DST: 3342-45'; packer failed.
DST: 3345-54'; packer failed.