

ET

21

31-21-11W

State Geological Survey

WICHITA BRANCH

DRILLER'S WELL LOG

DATE COMMENCED: 08/20/81
DATE COMPLETED: 08/27/81

Chapman Exploration, Inc.
MELLIES EASON Well No. 2
SE SE SW
Sec. 31, Twp. 21S, Rge 11W,
Stafford County, KS

ELEVATION: 1763' G.L.
1768' K.B.

FORMATION DATA:

3025 - 3065' Shale
3065 - 3155' Shale
3155 - 3172' Lime, shale
3172 - 3530' Lime
3530 - 3535' Dolomite
3535 RTD

Heebner 3025'
Douglas 3065'
Brown Lime 3155'
Lansing 3172'
Arbuckle 3530'
RTD 3535'

SURFACE PIPE:

Ran 7 jts. new 8-5/8" 20#
csg., Set @ 286' w/ 265 sks
60/40 poz., 2% gel, 3% cc.
(Tally: 279')
Cemt. circ., plug down 4:30 AM
8/21/81, by Howco

PRODUCTION PIPE:

Ran 96 jts. 9.5# 4 1/2" csg.
Tally: 3565', Set @ 3537'
w/ 150 sks 50/50 poz., 18%
salt, 15 CFR2, plug down @
11:50 AM, 8/27/81, by Howco

A F F I D A V I T

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS)
COUNTY OF BARTON) ss.

SEP 15 1981

CONSERVATION DIVISION
Wichita, Kansas

Greg Davidson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best