

DEC 5 1970

19-21-11W
NW SW NW
P 25 BO + 1/4
ac

DRILLERS LOG

No. 2 Cook

CASING RECORD:

8 5/8" @ 267.50'
w/225 ex cement

5 1/2" @ 3535'
w/125 ex cement

TOTAL DEPTH: 3541'

COMPANY: Oil Property Management

CONTRACTOR: Red Tiger Drilling Company

COMMENCED: April 4, 1970

COMPLETED: April 13, 1970

DESCRIPTION:

NW SW NW
19-21S-11W
Stafford County,
Kansas

ELEVATION: 1805' KB

FORMATION

FROM

TO

REMARKS

Sand	0	212
Red Bed	212	563
Gypsum	563	574
Anhydrite	574	582
Shale & Shells	582	1260
Shale	1260	1387
Shale & Lime	1387	2945
Lime	2945	3048
Shale	3048	3053
Lime & Shale	3053	3175
Lime (Brown)	3175	3200
Lime (Lansing)	3200	3240
Lime	3240	3458
Conglomerate	3458	3474
Simpson Shale	3474	3485
Simpson Sand	3485	3490
Simpson Sand & Shale	3490	3506
Arbuckle	3506	3541

(Salt 1387')

Log Left


Heebner 3047
Douglas 3082
Br Line 3173
Lansing 3188
Arbuckle 3515

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George R. Angle
George R. Angle, Owner

Subscribed and sworn to before me this 14th day of April, 1970.



Gloria Fawcett
Notary Public