

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - HARRY GORE & VEEDER SUPPLY & DEV. CO.
Farm - Peterson No. 1

SEC. 6 T. 21 R. 11W
~~SE SE NE C SE SE NE~~
~~CS 1/2 NW 1/4 NE~~

Total Depth. 3475
Comm. 3-14-50 Comp. 3-27-50
Shot or Treated.
Contractor. Veeder Supply
Issued. 4-29-50

County. Stafford
KANSAS



Elevation. 1830

Production. Dry

CASING:

8 5/8" 265' cem w/175 sx.
5 1/2" 3434' cem w/100 sx.

Figures Indicate Bottom of Formations.

sand gravel	220	4-5-, run tubing & acidize Acid w/1000 gals.
red bed	550	getting ready to swb thru 2 1/2" upset.
shale shells	1280	4-6, 43" oil in tank at 10:00 a.m.
shale	1425	4-7-, ready pull tubing. pulled 55 jts.
lime shale brks	1510	Bailing hole, run swb.
limeshale	2095	4-8-, 3457-3459,
shale shells	2200	3459-3464
lime shale	2320	3464-3468
shale	2450	3468-3473
shale shells	2570	3473-3475
lime shale shells	2690	4-9-, cleaning out on top of tools and drove tools
shale shells	2790	down 100'.
shale lime shells	2830	4-10, string tools to rip 5 1/2" casing after ripping
lime	2875	pipe off hole filled up w/mud and water.
limeshale	2940	4-11, pulled 83 jts. 5 1/2" casg. hole filled w/mud
shale shells	2990	to 265', put in bridge at 265'. Rock & 15 sx. cement
lime shells shale	3090	broke down tools.
shale shells	3140	4-12, tore down rig.
shale	3146	
lime	3370	
lime shale	3390	
conglomerate shale	3424	

R.T.D.

CABLE TOOL:

ar buckle	3421-23
dolo. arb.	3424
arb. lime hrd	3426
lime	3475
Total depth	

Tops:

Heebner	3005
Brown lime	3128
Lansing	3143
Conglomerate	3397
Simpson	3403
Ar buckle	3416

REMARKS: Cable tool drill-in.

3-29, Rigging up and stringing tools.
Bailed hole dry
3-30, run measuring line and laid water line. Drilled cement and plug, bailing hole.
Drilled cement 3391-3421, show oil 3417-3419.
Drilled Arb. 3421-23, some free oil.
Put in 100 gals acid.
3-31- Drilled 3423-3424, dolomite arb. shot well swbd well dry, cleaning out. Bailing & testing, shows little oil.
4-1, shot by Lane well from 3419-3423, nine shots.
Put in 1000 gals acid, Swbd and bailed 1 1/2 bailers pr hr.
4-2, 3424-3425, no inc. in oil.
3425-3426, ar buckle lime hrd.
3426-3430, show oil.
3430-3435, no inc.
3435-3440, show oil & little gas.
3440-3444, good show oil.
Hole filled up 200', 1 1/2 hrs.
4-3-, laying flow line & swb 8 1/2" oil in tank.