

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
 508 E. Murdock, Wichita, Kansas

Company - PHILLIPS & HANSON
 Farm - Ringering No. 1

SEC. 6 T. 21 R. 11W
 CE/2 W/2 NW

Total Depth. 3518
 Comm. 6-30-50 Comp. 7-26-50
 Shot or Treated.
 Contractor. Penguin Petro.
 Issued. 8-12-50

County. Stafford

KANSAS



Elevation. 1825 D.F.

Production. Dry

CASING:
 8 5/8" 272'
 5 1/2" 3458' corr.

Figures Indicate Bottom of Formations.

sand & gravel	210
red bed	272
red rock	607
lime, anhyd.	619
red rock	715
shale & shells	1465
shale & lime	1610
lime brkn	1830
lime & shale	1975
shale	2050
lime brkn	2180
shale & shells	2645
shale	2707
shale sdy	2743
lime	3105
shale	3160
lime	3410
shale	3465
R.T.D. 3465' = 3463' drill pipe corr. to top of hole R.U.S.T.	
dolo.	3518
Total Depth	

Tops: corr.	
Topeka	2740
Heebner	3016
Brown lime	3134
Lansing-K.C.	3156
Simpson shale	3421
Arbuckle	3457

Completion data:
 3465' = 3463' drill pipe corr. to top of hole R.T.D. 3463' corr. 5 1/2" 3458' corr. drill plug
 show of oil & gas
 drilled deeper to 3518
 water @ 3500
 ran radioactive log. Set Lane Wells plug @ 3330 Per. 47 shots 3292-3300
 Swab 2 BWPH