


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PRODUCERS PIPE & SUPPLY -- VEEDER SUP. & SEC. 6 T. 21 R. 11W
Farm- Diets No. 1 DEVL. CO. NE NW SE

Total Depth. 3451
Comm. 6-16-52 Comp. 6-26-52
Shot or Treated.
Contractor. Veeder Supply & Dev. Co.
Issued. 9-20-52

County Stafford
 KANSAS



CASING:
8 5/8" 329' cem. w/160 sx
5 1/2" 3410' cem. w/150 sx

Elevation. 1818

Production. Pot. 165 bbls.

Figures Indicate Bottom of Formations.

sand, shale	40
sand gry shale	225
red bed	329
shale	575
anhydrite	605
shale	1065
shale, shells	1545
lime brkn	1600
shale, shells	1725
lime, shale	2160
shale, shells	2565
shale, lime, shells	2735
lime, shale	2800
lime	2990
lime, shale	3210
lime	3412 RTD
shoe & float	3412
wht fine crystal stained	
porous	3419
hrd lgt fine crystal	
dolomite	3423
cherty dolo. course	3426
drk gry shale	3427
shale gry	3428
cherty lgt dolo.	3430 1/2
lgt tan oil stained dolo.	3432
fine crystal dolo.	3433 1/2
lgt dolo. fine crystal	3435
800' oil in hole	3437
fine crystal dolo.	
cherty saturated	3441
coarse crystal dolo.	
1700' oil in hole	3447
caving	3451
Total Depth	

Tops:
Heebner 3003
Brown Lime 3125
Lansing-K. C. 3141
Conglomerate 3393
Simpson 3400
Arbuckle 3409