

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

Company SOHIO PETROLEUM COMPANY
Farm Bright No. 1

SEC. 18 T. 21 R. 11W
NW NE NW

Total Depth. 3502'

Comm. 11-3-47

Comp. 11-19-47

Shot or Treated. Acid.

Contractor

issued 2-7-48

County. Stafford

KANSAS



Elevation. _____

Production. Phy Pot 36 BO 15%
wtr.

CASING.

8-5/8" 592' Cem. W/320 Sx.
5-1/2" 3489' Cem. W/150 Sx.

Figures indicate Bottom of Formations.

rig	5
surface sand	15
shale	40
sand	125
shale	270
red bed	580
anhydrite	602
red bed	695
shale	900
shale shells	1130
salt shale	1310
shale & shells	1420
lime broken	1845
sand	1855
lime broken	1970
shale & shells	2650
lime broken	2670
lime	3050
lime broken	3090
shale	3184
lime	3437
conglomerate	3445
Simpson shale	3488
Arbuckle lime	3502

Total Depth

TOPS:

Anhydrite	580
Lansing	3187
Kansas City	3429
Simpson	3442
Arbuckle	3490
Total Depth	3502

SHOWS OF OIL, GAS, & WATER:

DST 3251-61. Open 30 min. Rec.
18' mud SSO, DST 3354-64. Open 30
min. Rec. 8' mud, N.S. Dst 3489-99.
Open 30 min. Rec. 65' oil-c. mud.
Sch. Run pipe, 5" 3490; DP & CO to
TD Corrected 3500 TD. B. 5 G. muddy
OPH 7 hrs. 500 A. Bail 3 hrs. Last
hr 2 1/2 BO. 1500 A. Test. S. 1 1/2 BO &
1/2 BHEE 7 hrs. Pop: Phy 36 BOPD
& 15% water.