


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LEE PHILLIPS OIL COMPANY
 Farm- Smith Estate No. 1

SEC. 19 T. 21 R. 11W
 NE NW SW

County Stafford KANSAS

Total Depth. 3551'
 Comm. 6-22-56 Comp. 7-3-56
 Shot or Treated.
 Contractor.
 Issued. 4-13-57



Elevation. 1798' KB

Production. 25 BOPD

Figures indicate Bottom of Formations.

sand & shale	70
sand	185
red bed	250
red bed & shale	415
sand	455
red bed & sand	554
Anhydrite	568
shale	740
shale & shells	1430
lime & shale	2770
lime, chert, shale	2845
lime & shale	2980
lime & chert	2992
lime, chert, shale	3061
shale & lime	3190
lime	3346
lime & shale	3398
lime	3458
Conglomerate	3499
lime	3512
Arbuckle	3516 RTD
lime ?	3551 CTD
Total Depth	

Ran electric log

TOPS	
Anhydrite	554
Heebner	3039
Brown lime	3166
Lansing/Kansas City	3190
Base/Kansas City	3424
Conglomerate	3458
Simpson	3490
Arbuckle	3510

DRILL STEM TESTS

DST #1 3337-46 op. 1 hr.
 good steady blow, Rec. 60'
 black hocrn, 840' gas.
 BHP 925#.
 DST #2 3510-14 op. 1 hr. good steady
 blow, rec. 120' froggy oil,
 800' gas. BHP 440#

Perf. 3481-86 w/48 holes.
 Fractured w/sand & oil.
 Swab 5 BOPH decreased to
 approx. 20 BOPD.