


VIRGINIA DRILG.CO.,INC. ET AL
Estey No. 1.

SEC.25 T.21 R. 11 W
CW $\frac{1}{2}$ SW NE

Total Depth. 3500'
Comm. 11-7-42 Comp. 11-26-42
Shot or Treated.
Contractor: Virginia Drilg.Co.,Inc.
Issued. 12-26-42

County: Stafford



CASING:
8 5/8" 205'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

surface clay	20	Tops:
sand & clay	95	K. C. 3090
reamed 40' to 11"		C. Cong. 3374
sand & shells	40-185	Simpson 3408
shale & shells	205	
reamed 185-205		
run 205' of 8 5/8 cas.		
sand & shale	235	
shale & shells	250	
red bed	445	
anhydrite	465	
shale	660	
shale & shells	1025	
salt & shale	1075	
shale sft	1290	
lime	1310	
lime & shale	1405	
lime shells	1490	
shale & lime shells	1615	
lime	1700	
lime sdy	1785	
shale	1800	
lime	1850	
sand	1860	
lime	1920	
shale & lime	1950	
lime	2030	
lime & sdy shale	2135	
lime & shale	2215	
shale & shells	2315	
shale	2390	
lime	2465	
shale & shells	2510	
lime	2670	
lime w/shale stops	2725	
lime	2970	
shale	3073	
lime	3136	
lime sft	3140	
lime	3168	
lime sft	3186	
lime	3377	
cherty conglomerate	3407	
lime	3408	
sand	3430	
lime sdy	3445	
shale	3467	
sm sh gas	3418	
Arbuckle lime	3500	
Total Depth.		

1746
445

x1301