


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- RAYMOND OIL & CHAMPLIN REFINING CO.  
Farm- Dortha Eriksen No. 1

SEC. 27 T. 21 R. 11W  
NW NW NW

Total Depth. 3537'  
Comm. 7-28-59 Comp. 8-7-59  
Shot or Treated.  
Contractor. Raymond Oil Co.  
Issued. 11-14-59

County Stafford  
KANSAS



Elevation. 1740' DF

CASING:

8 5/8" 293' cem w/300 sx.

Production. Dry

Figures Indicate Bottom of Formations.

surface hole, sand	165
red bed, shale & shells	293
red bed	460
Anhydrite	500
shale & shells	1150
salt	1300
lime & shale	2435
shale & lime	2665
lime with shale	2775
lime & shale	3181
lime	3298
lime with shale	3362
chert	3400
sand	3412
lime & shale	3418
shale & lime	3453
dolomite	3537 RTD
Total Depth	

TOPS:

Anhydrite	460
Topeka	2657
Heebner	2952
Toronto	2968
Douglas	2986
Brown Lime	3084
Lansing	3101
Conglomerate	3364
Simpson Sand	3402
Arbuckle	3453