

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- NORTH AMERICAN PRODUCTION CO.  
Farm- Hullman No. 1

SEC. 30 T. 21 R. 11W  
SW SW SE

Total Depth. 3516  
Comm. 1-16-51  
Shot or Treated.  
Contractor.  
Issued. 12-24-55

Comp. 2-3-51

County Stafford  
KANSAS



Elevation. 1770

CASING:  
8 5/8 5 joints w/ 100 sx cmt.  
5 1/2 @ 3506' w/ 100 sx cmt.

Production. 282 BOPD, trace W

Figures indicate Bottom of Formations.

clay & sand	40
sand & red bed	198
red bed & shale	455
shale & shells	555
anhydrite	590
shale & shells	1375
Ft. Riley lime	1585
lime & shale	1860
shale & shells	2050
shale & lime	2770
lime	2985
lime & iron	3055
lime	3155
lime & shale	3182
Lansing lime	3215
lime	3320
sandy break	3328
dense lime	3350
lime & shale	3410
lime	3465
shale & conglomerate	3480
conglomerate	3495
Simpson sand	3516
Total Depth	

SCOUT TOPS:	
Heebner	3030
Brown lime	3162
Lansing	3180
Conglomerate	3450
Viola	3469
Simpson shale	3486
S impson sand	3503