


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HEXAGON OIL CO., & MIDGE OIL CO.
Farm- Duggan No. 3

SEC. 30 T. 21 R. 11W
SW NW SW

Total Depth. 3536
Comm. 7-8-51 Comp. 7-20-51
Shot or Treated.
Contractor. Pickrell Drilling Co.
Issued. 9-27-52

County Stafford
KANSAS



CASING:

10 3/4" 241' cem w/160 sx in 13 3/4" hole circ.
5 1/2" 3516' cem w/150 sx in 9" hole

Elevation. 1793

Production. 22 bbls / 2% water

Meas. from top rotary bushing. Figures indicate Bottom of Formations.

sand	125
shale, shells	200
red bed	241
red bed, shells	542
anhydrite	570
shale, shells	1490
shale, lime	1590
sand	1608
lime, shale	2365
shale, shells	2530
shale, lime	2800
lime	3167
shale	3175
lime brown	3190
Kansas City lime	3260
lime	3459
conglomerate	3513
simpson	3516
lime arbuckle	3521
arbuckle	3523 RTD
arbuckle	3536
Total Depth	

Tops: Scout.
Lansing 3190
Conglomerate 3470
Simpson 3497
Arbuckle 3516

SLM at 3000 O.K.