

33-21-12 West

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - ARTNELL CO.
Farm: Sittner

No. 3

SEC. 33 T. 21 R. 12 W
SW NE NE

Total Depth. 3605'
Comm. 1-16-46 Comp. 5-22-46
Shot or Treated.
Contractor.
Issued. 9-7-46

County. Stafford
KANSAS



Elevation. 1857 ft.

Production. Pump 40 BO, no wtr.

CASING:

10" 272'
5 1/2" 3600'

Figures Indicate Bottom of Formations.

Made from sample log
No log above 3175'

shale	3175-78
lime	3181
shale	3210
shale sdy	3240
shale	3254
lime	3261
shale	3271
lime	3280
lime some chert	3295
lime fair por.	3300
lime no por.	3310
lime	3330
shale	3332
lime	3480
shale	3482
lime	3496
shale red w gy	3505
shale, sand, chert	3510
chert	3544
dolomite & chert	3550
lime	3552
shale sdy	3580
shale green sdy	3599
sand	3600
dolomite	3605

Total Depth.

Tops:

Brown Lansing	3254
Lansing	3271
Base Kans. City	3496
Viola	3510
Dimpson	3550
Arbuckle	3600

Perf. to 3440-00', made gas
& filled 00' w/oil.
5000 acid through perf. 3440-00'.
Flowed approx. 100 oil &
100 wtr.
1-16-46 P. S. 3306-3402'.
1000 gals. acid.