

3-21-12W


KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY ASPEN DRILLING
 FARM Wolf NO. 1

SEC. 3 T. 21 R. 12W
 LOC. SE SW SE

TOTAL DEPTH 3484
 COMM. 8-2-66 COMP. 8-11-66
 SHOT OR TREATED
 CONTRACTOR Aspen Drlg.
 ISSUED 12-10-66

COUNTY Stafford



CASING

20	10	
15	8 5/8"	@ 250' w/250 sx
12	6	
13	5 1/2"	@ 3479' w/140 sx

ELEVATION 1858' KB

PRODUCTION PMP 106 BOPD, NW
 GR 30.6 (Arb 3479-84)
 FLO 202 BOPD, NW GR 26 12/64" CK
 (Lans 3277-84)

FIGURES INDICATE BOTTOM OF FORMATIONS

FORMATION

DEPTH

Sandstone & Clay	160
Shale	220
Red Bed	632
Anhydrite	662
Shale & Shells	1490
Limestone & Shale	1630
Limestone	1920
Limestone & Shale	2894
Limestone	3480
RTD	3480

Spudded @ 4:45 P.M., 8-2-66
 Drilled 12 1/4" hole to 252', ran 12 jts
 (242') used 8 5/8" casing. Set @ 250'
 w/250 sx sunset. Plug down @ 1:00 A.M.
 8-3-66.

DST #1	-	3213	-	60
DST #2	-	3263	-	3285
DST #3	-	3289	-	3295
DST #4	-	3360	-	3420
DST #5	-	3474	-	3480

Ran electric log.

Ran 112 jts. 5 1/2" 14# J55 Casing.
 Set @ 3479', cemented w/140 sx 50/50
 Lt. Poz, 2% Gel, Salt Saturated, 0.1%
 T.I.C., 2% D33A. Plug down @ 5:05 A.M.
 8-11-66.

FORMATION TOPS

Anhydrite	637 (+1221)
Heebner	3066 (-1208)
Brown Lime	3198 (-1340)
Lansing	3212 (-1354)
Arbuckle	3471 (-1613)
Rotary Total Depth	3480 (-1622)