

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

17-21-12W

Company FRED B. ANSCHUTZ
Farm Heaton

No. 1

SEC. 17 T. 21 R. 12W
NE SW SW

Total Depth. 3552

Comm. 1-14-50


Comp. 1-26-50

Shot or Treated.

Contractor.

Issued. 3-11-50

County. Stafford
KANSAS



Elevation. 1871 *ft*

CASING:
8 5/8" sur. csg set at 305', cem. w/200
sx cement
5 1/2" csg. set at 3539', cem. w/75 sx
cement
Figures Indicate Bottom of Formations.

Production. Phy. Pot. 163 BO
& NW

sand	230
redbed	680
anhy.	700
shale & shells	1250
salt	1355
shale & shells	1500
lime	2008
shale & lime	2140
shale & shells	2175
lime broken	2285
shale & lime	2750
lime	2795
shale & lime	2885
lime	3185
shale & lime	3277
lime	3494
shale & lime	3514
shale & lime	3536
Arbuckle limo, R .T.D.	3540
lime	3552
Total Depth	

Measurements corrected to derrick floor:

Tops :

Heebner	3118
Toronto	3135
Brown Lime	3249
Lans.-KC	3265
Conglomerate	3485
Simpson	3491
Arbuckle	3535