

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock,
Wichita, Kansas


17-21-12W

Company- ANSCHUTZ DRILLING COMPANY
Farm- Heaton No. 8

SEC. 17 T. 21 R. 12W
NW SW SW

Total Depth. 3710
Comm. 10-15-51 Comp. 11-3-51
Shot or Treated.
Contractor.
Issued. 7-11-53

County Stafford
KANSAS



CASING:
8 5/8" 320 cem w/225 sx
5 1/2" 3709' cem w/125 sx

Elevation. 1866

Production. 306 bbls / 22% wtr

Figures indicate Bottom of Formations.

sand, red rock	290
shale, shells	320
shale red	650
red bed	660
anhydrite	700
shale	100
shale, shells	1175
salt	1350
shale, lime	1625
lime	1970
lime, shale	2285
shale	2450
lime, shale	2700
shale	2800
shale, lime	2900
lime	3190
shale, lime	3250
lime	3515
shale, lime	3532
lime (coring)	3630
Reaming	3632
lime (Coring)	3710
Reaming	3710
Total Depth	

Tops: Scout	
Heebner	3106
Toronto	3133
Brown Lime	3237
Lansing	3252
Congl.	3470
Simpson	3481
Arbuckle	3537