

19-21-12W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - MID-CONTINENT PETRO. CORP.
Farm - Karl Fisher No. 2

SEC. 19 T. 21 R. 12W
S. 2 NW SW

Total Depth. 3611
Comm. 6-8-46 Comp. 6-26-46
Shot or Treated. 1500 acid
Contractor. Barnett Drlg. Co
Issued. 8-10-46

County. Stafford
KANSAS



CASING:

9 5/8" 298'
5 1/2" 3606'8"

Elevation. 1866 ft

Production. 222 Bbls.

Figures Indicate Bottom of Formations.

surface clay	41
sand	220
red bed	280
red bed & shale	306
red bed	700
anhydrite	725
shale & shells	1240
salt & shale	1320
shale	1540
lime & shale	1705
lime	1755
sandy lime	1825
limo & shale	1930
limo	1985
shale & lime	2205
shale	2275
lime & shale	2410
shale	2470
lime & shale	2635
lime	2745
shale & limo	2775
limo	2855
limo & shale	2886
lime	3140
shale & lime	3180
limo	3190
shale	3242
lime	3441
lime & chert	3447
lime	3514
chert	3520
limo	3533
shale	3581
lime & shale	3589
lime, shale chert	3603
limo	3611
Total Depth	

Tops:	
Anhydrite	700
Lansing	3296
Viola	3518
Arbuckle	3589

