

19-21-12W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MAGNOLIA PETRO.
Farm- E.B. Hall No. 6

SEC. 19 T. 21 R. 12W
NW NE NW

Total Depth. 3687'
Comm. 6-29-56 Comp. 7-15-56
Shot or Treated.
Contractor. Mallonee Drlg. Co.
Issued. 8-25-56

County Stafford
KANSAS



CASING:
9 5/8" 217' w/250 sx cem.

Elevation. 1863

Production. Dry

Figures indicate Bottom of Formations.

surface-sand	20
shale-sand	317
red rock-sand	340
red bed-sand	700
Anhydrite	730
shale	1020
shale-red bed	1430
shale-lime	2295
shale-shells	2660
shale-lime	3090
lime	3150
shale-lime	3277
lime	3535
Conglomerate-lime	3615 #1
lime	3630 #1,2
lime-chert	3634 #2,3
lime	3658 #3
cherty lime	3672
lime	3687
Total Depth	

TOPS:

Heebner	3145
Toronto	3163
Brown limestone	3274
Lansing-Kansas City	3291
Conglomerate	3530
Simpson	3559
Arbuckle	3605

DST #1, 3607-20, miss run,
no test

DST #2, 3607-34, miss run,
no test

DST #3, 3526-58, miss run,
no test.