

19-21-12W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - STANOLIND OIL & GAS CO.
Farm - E. B. Hall No. 3

SEC. 19 T. 21 R. 12W
NE SE NE
990' N. of S.L. 330' W. of
E.L. of NE/4
County. Stafford

Total Depth. 3552
Comm. 6-15-51 Comp. 6-28-51
Shot or Treated.
Contractor.
Issued. 9-1-51

KANSAS



CASING:
10 3/4" 684' cem. w/425 sx
5 1/2" 3545' cem. w/150 sx

Elevation. 1866 RDB
1862 (2nd)
Production. 1588 BO

Figures Indicate Bottom of Formations.

| | |
|--|----------|
| sand | 240 |
| red bed | 300 |
| red bed, shale, shells | 635 |
| shale | 677 |
| anhydrite | 705 |
| red bed, shale, shells | 985 |
| red bed, shells | 1220 |
| salt, shells | 1360 |
| shale, shells | 1620 |
| shale, lime | 3260 |
| shale, lime | 3287 |
| lime, S.S. Oil | 3305 |
| lime | 3328 |
| lime, show oil | 3347 |
| lime | 3376 |
| lime, show of oil | 3446 |
| lime | 3535 |
| sand, shale, lime oil & show of gas | 3552 RTD |
| Total Depth | |

| | |
|----------|------|
| Tops: | |
| Lansing | 3260 |
| Arbuckle | 3541 |

Acidized with 500 gal. Dowell
XX Acid down casing into
formation.

Schlumberger T.D. 3552
Test: 6 hr. swab test, 11 BOPH,
no wtr.
Landed 2 1/2" tubing @ 3521
State Pot. 3-rate D.D. 1588
no wtr.