

PZ
State Geological Survey
WICHITA, BRANCH

15-185-21029
19-21-12W

DRILLER'S WELL LOG

DATE COMMENCED: 3-15-80
DATE COMPLETED: 3-22-80

Evan Jantz & Associates
Helen Hull #1 HALL
S/2 NW NE - Sec. 19-21-12
Stafford County, Kansas

ELEVATION: K.B.
1860' G.L.

FORMATION DATA

Anhydrite

107-3112' Shale
3112-3257' Lime and Shale
3257-3273' Lime and Shale
3273-3501' Lime
3501-3535' Chert
3535-3610' Sand
3610-3660' Dolomite
3660' RTD

Anhydrite

Heebner 3107
Brown Lime 3257
Lansing 3273
Viola 3501
Simpson Sand 3535
Arbuckle 3610
RTD 3660

SURFACE PIPE:

Ran 7 Jts. Used 8 5/8" Casing.
Tally 302'. Set @ 303' w/250 sks.
50-50 Pozmix, 2% Gel, 3% c.c.
Cement did not Circulate - 1" w/50 sks.
By Howco. P.D. @ 4:30 p.m.

PRODUCTION PIPE:

Ran 93 Jts. 5 1/2" 14#. Set @ 3659'
w/125 sks. 60-40 Pozmix, 2% Gel Salt
By Howco. P.D. @ 5:15 p.m.

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

RON DENNER, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.