

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas

2621-12W

Company- ALLAN & SHAWVER-ARMOUR DRILLING CO.
Farm- Widener No. 1

SEC. 26 T. 21 R. 12W
NW NE SE

Total Depth. 3655'

Comm. 11-15-56


Comp. 11-27-56

Shot or Treated.

Contractor. Tom Allan

Issued. 12-15-56

County Stafford
KANSAS



Elevation. 1828' RB

CASING:

8 5/8" @233' w/225 sx cem.

Production. Dry

Figures indicate Bottom of Formations.

ALL DEPTHS FROM ROTARY BUSHINGS

soil & sand	45
Coarse Gravel	140
yellow clay	160
blue gumbo	190
red beds	233
red shale	596
Anhydrite	616
red shale	850
shale	1000
salt & shale	1300
shale & Anhydrite	1500
shale & lime	1825
Fossiliferous Lime	1858
red shale	1865
shale & shells	2200
shale	2800
lime	3110
black shale	3114
lime	3120
shale	3136
lime	3145
shale	3240
brown lime	3245
shale	3259
lime	3300
lime & shale	3325
lime	3352
Oolitic lime	3355
lime	3398
Oolitic lime	3401
lime	3435
Porous Oolitic lime	3440
lime	3450
shale	3457
lime	3503
shale	3513
lime	3518
red shale, little Vari	
color Chert	3548
white, & Vitreous Chert	
show dark oil	3592

DRILL STEM TEST:

DST #1, 3551-3593 20' mud
60 min. BHP 50#/45 min.

green & red shale	3638
buff Crystalline	
Dolomite Porous w/pet.	
residue	3655
Total Depth	

RAN HALLIBURTON ELECTRIC LOG

TOPS	
Anhydrite	596
Base/Florence Flint	1858
Heebner	3110
Brown lime	3240
Lansing	3259
Conglomerate	3518
Viola Chert	3548
Simpson	3592
Arbuckle	3638