

32-21-12W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

Company G. W. KEYES DRILLING CO.
Farm Umstead "B" No. 1

SEC. 32 T. 21 R. 12W
CN $\frac{1}{2}$ SW NE

Total Depth. 3646'

Comm. 2-4-48


Comp. 2-21-48

Shoreline Record.

Comm. Record.

Shoreline 7-10-48

County. Stafford
KANSAS



Elevation. 1867' End.

Production. Dry

Figures indicate Bottom of Formations.

sand	0-212
shale	242
red bed	661
anhydrite	695
shale & shells	1170
salt & shale	1495
lime	1550
lime & shale	1680
lime brkn	1825
lime	1975
lime brkn	2055
shale & shells	2830
lime	2935
lime brkn	3055
lime	3205
lime & shale	3270
lime	3510
shale	3522
conglomerate	3554
Viola lime	3578
shale	3589
cherty cong. & shale	3605
shale	3610
lime RTD	3619

Moved in cable tools, bailed
hole, drilled cement and cleaned
out hole to total rotary depth.
Drilled deeper.

lime 3646

Total Depth

Tops: (Corr. 3' to D.F.)

Heebner Shale	3134
Base Oread	3165
Brown Lime	3263
Lansing	3287
Conglomerate	3518
Viola White Chert	3540
Simpson Shale	3575
Arbuckle Dolomite	3607