


TORREY AND FEASTER.
Mueller No. 1.

SEC. 29 T. 21 R. 12W.
SE SE

Total Depth. 3606
Comm. ~~1-26-38~~ 1-27-38 Comp. ~~3-29-38~~ 2-20-38
Shot or Treated.
Contractor.
Issued. 4-23-38

County Stafford.



CASING.

12" 248' 5" 3594'

Elevation.

Production. Pot. 1210 B.

Figures Indicate Bottom of Formations.

sand	215	K.C. lime	3337
red beds	257	lime	3430
red rock	685	cored from 3350 to 3 355	
shale	895	Run steel line at 3390	
shale and lime		no correction.	
shells	1029	lime and shale	3480
shale and shells	1140	Viola lime and	
salt	1184	conglomerate	3528
salt and shale	1380	Viola lime	3536
shale and shells		Simpson series	3546
and salt	1444	Simpson	3590
shale and lime		shale green	3592
shells	1470	2 ft correction.	
lime and shale	1496	Siliceous lime	3600
lime	1670	Fine showing.	
lime and shale	1724	siliceous lime	3606
lime	1743	Total Depth.	
lime and shale	1895		
hd sdy lime	1906		
lime and shale	2320		
shale	2396		
shale	2593		
shale and lime			
shells	2700		
lime and shale	2758		
shale and lime			
shells	2790		
lime and shale	2867		
lime Topeka	2960		
lime brown	3023		
lime	3026		
broken lime	3051		
lime	3134		
lime hard	3160		
lime & shale	3173		
shale and lime			
shells	3276		
lime K.C.	3301		
Top K.C. lime	3276		
broken lime	3305		
lime	3310		