


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANSCHUTZ DRILG. CO.
Farm- Fischer "A" No. 2

SEC. 31 T. 21 R. 12W
CW/2 NW NW

Total Depth. 3715
Comm. 8-25-51 Comp. 10-14-51
Shot or Treated.
Contractor.
Issued. 2-23-52

County Stafford
KANSAS



CASING:
8 5/8" 325' cem. w/175 sx
5 1/2" 3715' cem. w/175 sx

Elevation. 1872 DE

Production. 868 BO & 21% wtr.

Figures Indicate Bottom of Formations.

surface clay	30
sand	240
red shale	270
sand	300
red shale	680
anhydrite	712
shale	1100
shale & salt	1400
shale & lime	1750
lime	2020
lime & shale	2090
lime	2160
shale & lime	2340
shale	2450
shale & lime	2735
shale	2885
lime & shale	2985
lime	3215
shale	3285
lime	3525
lime & shale	3552
viola chert	3570
lime	3605
shale & lime	3626
lime	3715
Total Depth	

Tops:	
Heebner	3152
Brown Lime	3280
Lansing	3296
Viola	3540
Reworked Arbuckle	3619
Solid Arbuckle	3630

DST: 3414-26 open 3 min.
rec. 60' oil & gas cut mud,
DST: 3452-64 open 15 mins.
rec. 1900' gas & 30' oil
cut mud & 60' muddy oil BHP
1010#,
DST: 3496-3502 open 40 min.,
rec. 10' slightly oil cut mud,
BHP 170#.,
DST: 3621-26 open 40 min. no rec.
This is all the information that
will be released on this well.
The electric log is not to be
released.