

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - STANOLIND OIL & GAS CO.
Farm - J. K. Fisher No. 3

SEC. 31 T. 21 R. 12 W
NW SE SW
990' N SL & 1650' E WL SW $\frac{1}{4}$

Total Depth. 3622'

Comm. 5-18-44

Shot or Treated.

Contractor.

Issued. 7-15-44

Comp. 6-9-44

Rotary 0-3620

Cable 3620-3622

County.

Stafford
KANSAS



CASING:

8 $\frac{5}{8}$ "

5 $\frac{1}{2}$ "

236' Cem.

3617' 8" Cem.

Elevation. _____

Production. Pot. 1279 B.
2% wtr, Drawdown

Figures Indicate Bottom of Formations.

surface clay	0-227
red bed	236
red shale	380
red bed	682
anhydrite	704
shale	880
red shale & shells	1110
lime & shale	1235
salt & shale	1515
lime broken	1725
lime	1765
shale & lime	1850
shale	1920
lime broken	1980
shale & lime	2030
lime	2165
shale & shells	2255
shale	2550
lime broken	2605
lime	2655
lime broken	2830
lime & shale broken	2886
lime	2970
lime & shale	3040
lime sandy	3085
lime	3155
shale & lime	3268
lime	3276
shale	3305
lime	3527
chert	3555
chert & lime	3562
shale	3618
dolomite	3622
Total Depth.	

Tops:

Lansing	3290
Conglomerate	3527
Arbuckle	3618