


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

STANOLIND OIL AND GAS CO.
G.W.Walker No. 2

SEC. 33 T. 21 R. 12W.
CS $\frac{1}{2}$ NW SW
1650' NSL 660'EWL SW $\frac{1}{4}$

Total Depth. 3649
Comm. 3-28-41 Comp. 4-18-41
Shot or Treated.
Contractor.
Issued. 5-31-41

County Stafford.



Rotary
CASING.

85/8" 284'8"
6 $\frac{1}{2}$ " 3644.11"

Elevation.

Figures Indicate Bottom of Formations.

Production. Pot. 43 B. 8H.
Phy., 19% Wtr

cellar	30
sand	264
red bed	667
anhydrite	700
red bed shale and shells	780
shale lime shells	1190
shale and salt	1490
lime	1660
broken lime	1725
shale	1800
lime	1815
broken lime	2280
shale	2605
broken lime	2830
lime	3190
broken lime	3254
shale	3288
lime	3528
lime and chert	3587
shale	3644
dolomite	3649

Total Depth.

Arbuckle 3644-3649

Natural 3/4 BOPH and trace water.

Physical Potential - pumped 43 bbls oil in 8 hours, 19% water.