


49414 ✓

STANOLIND OIL & GAS CO.
K. Krentzel No. 1.

SEC. 34 T. 21 R. 12W
NW NW NW
2310' N SL 330' E WL

County. Stafford

Total Depth. 3409'
Comm. 9-1-37 Comp. 9-23-37
Shot or Treated. 3000 Gals.
Contractor.
Issued. 1-8-38 Rotary O-3409



CASING:
13" 238'9"
8 5/8" 3368'11"
5 1/2" 3327'4"

Elevation.

Figures Indicate Bottom of Formations. Production. Pot. 1827 B.
No wtr.

surface sand	215	Lansing 3276-3409
shale & red rock	494	Flowed 139 Bbls. oil 45 min. after acid.
shale	645	State Pot. 1827 Bbls. oil, no wtr.
shale & lime shells	1273	
salt & shells	1375	
shale & lime shells	1505	
lime	2198	
lime & shale	2257	
lime	2693	
lime & shale	2839	
lime	3026	
shale & lime	3063	
lime	3103	
chert & lime	3135	
lime	3177	
shale & lime	3276	
Lansing lime	3365	
Top Lansing lime 3276		
Coring Record		
3/15' Recovery Lansing		
dense with sm sat.	3380	
lime drilled	3395	
lime dense with sm show oil		
(cored)	3399	
lime tan very oolitic w/ good		
porosity & show of oil	3405	
lime tan dense with slight sh		
of oil	3409	
Total Depth.		