


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- E.H. ADAIR OIL
Farm- Sittner No. 4

SEC. 35 T. 21 R. 12W
NE SE NW

Total Depth. 3590'
Comm. 5-1-56 Comp. 5-19-56
Shot or Treated.
Contractor. Mallonee Drlg. Co
Issued. 7-21-56

County Stafford
KANSAS



CASING:

8 5/8" 313' w/200 sx cem.
5 1/2" 3588' w/100 sx cem.

Elevation. 1830 KB.

Production. Swabbed 12 BOPH-
natural, NW

Figures indicate Bottom of Formations

sand-clay	165
gravel	195
red bed-sand	525
red bed-shale	1445
lime-shale	1600
lime	2355
shale-lime	2905
lime	3095
shale	3100
lime	3126
shale	3224
lime	3232
shale	3244
lime	3500
shale	3506
chert-shale	3531
shale	3583
sand	3587
Dolomite	3590
Total Depth	

TOPS: Scout

Heebner	3095
Toronto	3116
Douglas	3126
Brown lime	3224
Lansing	3244
Viola	3506
Simpson	3531
Arbuckle	3587