


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- E. H. ADAIR OIL CO. & LEE PHILLIPS OIL CO. SEC. 35 T. 21 R. 12W
 Farm- Sittner No. 5
 Approx. NW SE NW
 820' fr EL & 1000' fr SL
 of NW/4

Total Depth. 4010'
 Comm. 10-2-58 Comp. 10-16-58
 Shot or Treated.
 Contractor. Raymond Oil Co.
 Issued. 12-20-53

County Stafford
 KANSAS



Elevation. 1834' KB

Production. 50 BCPD

CASING:

8 5/8" 267' cem w/225 sx.
 5 1/2" 3800' cem w/200 sx.

Figures Indicate Bottom of Formations.

sand	175
redbeds	250
shale	620
Anhydrite	632
shale	1420
shale & lime	3000
lime	3101
black shale	3106
lime	3110
shale & lime	3129
lime	3134
shale	3233
lime	3236
shale	3255
lime	3295
porous lime	3297
lime	3329
porous lime	3333
lime	3447
porous lime	3450
lime	3507
sandy shale	3523
Conglomerate	3538
shaley chert	3565
shale	3610
dolomite, show of oil	3680
dolomite	4010 RTD
Total Depth	

TOPS:

Heebner Shale	3101
Douglas Shale	3134
Brown Lime	3233
Lansing-Kansas City	3255
Cherty Conglomerate	3523
Viola	3538
Simpson	3565
Arbuckle Dolomite	3610