


H. L. ROWLEY
Sittner No. 1.

SEC. 35 T. 21 R. 12W
SEc NE

Total Depth. 3575'
Comm. 7-27-38 Comp. 8-25-38
Shot or Treated.
Contractor.
Issued. 10-15-38

County. Stafford



CASING:
10" 263'
7" 3565'

Elevation.

Production. Pot. 1230 B.

Figures Indicate Bottom of Formations.

surface	10	Top Anhydrite	620
olay white	40	Top Ft. Riley	1740
sand	200	Top Topeka	2830
red rock	275	Top Kansas City	3235
sand	290	Top Conglomerate	3515
red rock	825	Top Simpson	3520
shale & lime shells	1000	Top Arbuckle	3565
shale & anhydrite	1380		
brkn lime	1615		
lime	1775		
brkn lime	1800		
lime	1825	Slight sh oil	3375-76
shale & lime	1912	Very drk oil	3384-85
lime	1950	Light sat.	3568-70
shale	2050		
brkn lime	2130		
shale & lime	2208		
lime	2245		
shale	2325		
lime & shale	2405		
brkn lime	2480		
shale	2560		
lime	2643		
shale & lime shells	2708		
lime	2712		
lime & shale	2792		
lime	3374		
lime cored	3385		
lime	3515		
chert (conglomerate)	3527		
Simpson	3555		
shale	3565		
Siliceous lime	3669		
2' corr to DF			
Cored	3570-	3575	
Total Depth.			