

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SOHIO PETROLEUM COMPANY
Farm - Schrepel No. 1

SEC. 12 T. 21S R. 12W
SEc SE

Total Depth. 3517'
Comm. 6-8-47 Comp. 6-22-47
Shot or Treated.
Contractor.
Issued. 9-20-47

County. Stafford
KANSAS



CASING:
8" 531' cem. 350 sx.
5" 3482' cem. 125 sx.

Elevation. _____

Production. Pot. 363 Bbls. oil

Figures Indicate Bottom of Formations.

Rig foundation	5
sand	150
shale & shells	235
red bed	593
anhydrite	620
shale & shells	1075
salt & shale	1255
shale & shells	1575
broken lime	1715
lime	1830
broken lime	1910
shale & shells	2710
shale	2765
broken lime	2975
lime	3040
broken lime	3085
shale	3170
brown lime	3178
shale	3186
Lansing Lime	3422
Conglomerate	3465
shale	3482
arbuckle lime	3517
Total Depth.	

GEOLOGICAL TOPS:

Anhydrite	595
Heebner	3044
Base Miss.	3168
Lansing	3184
Conglomerate	3426
Simpson Shale	3436
Arbuckle	3480

Soft & Show oil 3227-31, 3234-40, 3262-80, 3323-34, 3340-50, DST 3261-83, open 10 min. gas 6 min. Rec 500' G. cut muddy oil; TD 3515, Sch. DP & Clean out to 3515 TD, FU 2200' Oil, $1\frac{1}{2}$ 2900' Total POP. 32.4 Grav.

Ran Schlumberger test at 3517' good test.
Ran Halliburton test at 3283'.