

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg. Wichita, Kansas

Company - PHILLIPS PET. CO.  
Farm - Eveleigh No. 2

SEC. 13 T. 21 R. 12W  
SW NE NE

Total Depth. 3515 PB 3443'  
Comm. 10-2-47 Comp. 11-18-47  
Shot or Treated.  
Contractor.  
Issued. 6-5-48

County. Stafford  
KANSAS



CASING:  
8" 600'  
5" 3491'

Elevation. \_\_\_\_\_

Production. Dry

Figures Indicate Bottom of Formations.

surface soil	35	Drlg to 3495 with rotary tools,
sand & gravel	130	Drlg to 3515, 500 gal, Tested 7
shale	135	BO & 81.72 BW. Plugged back with
sand	195	cement to 3449. 12 shots 3409-13
red rock and shale	568	no shows, 12 shots 3405 to 09,
shells	580	small show oil, 12 shots 3401 to
anhydrite	650	3405, 3 shots to 3401, no show,
shale & shells	1520	56 shots 3370 to 84, 1500 gallons
lime & shale	1750	acid, tested 5 gals water per hr
lime, broken	1865	& small show oil in 8 hrs. Total
shale & lime	1945	44 shots from 3330-41, acid 500
shale & shells	2185	gals., test 6 gals water per hour
shale & lime shells	2355	for 19 hours.
shale & lime	2620	Set Lane-Wells plug at 3300, 60
shale	2665	shots 3270-85, 20 shots 3258-63,
lime, hard	2685	20 shots 3250-55, no shows, 1500
lime & shale	2840	gallons, bailed 4 bbls water and
lime	2984	scum of oil in 13 hours.
lime & shale	3043	Set Lane-Wells plug at 3246. 36
lime, broken	3125	shots 3227-36, 16 shots 3222 to
shale & lime	3170	26, 28 shots 3212 to 19, 72 shots
lime	3495	3189 to 3207, 1500 gallons acid,
lime	3515	tested 3 1/2 bbls water and scum of
Total Depth.		oil in 24 hrs.

P.B.T.D. 3443

TOPS:

Heebner	3038
Brown Line	3160
Lansing-Kansas C.	3180
3189-3197	Poor porosity, spotted stain
3202-3207	Very poor ", Very light "
3212-3217	Very poor ", slight stain
3222-3226	Very poor ", light "
3251-3255	Poor Porosity, very light stain
3258-3263	" to fair porosity, SFOil
3270-3276	Fair to good porosity, SFOil
DST 3280-3278	Rec. 30 feet mud
3316-3324	Poor porosity, very slight stain
3330-3336	" " " " "
3356-3362	" " " Spotted stain
	slight show free oil
3376-3384	Poor to fair porosity, spotted stain
	show oil DST 3352-84 Rec 8 ft. mud.
3399-3407	poor porosity, very light spotted stain.
Viola	3417
Simpson	3443
Arbuckle	3489