

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANSCHUTZ DRILLING CO.
Farm-Christiansen No. 2

SEC. 15 T. 21 R. 12W
SW NE SE

Total Depth. 3652
Comm. 12-11-52 Comp. 12-23-52
Shot or Treated.
Contractor.
Issued. 3-14-53

County Stafford
KANSAS



Elevation. 1847 RB

Production. 175 BO, 2% water

CASING:

8 5/8 set at 317' w/ 225 sx cement
5 1/2 set at 3651' w/ 100 sx cement

Figures indicate Bottom of Formations.

sand & clay	150
shale & shells	315
red shale	475
red bed	640
anhydrite	660
shale	975
shale & shells	1175
salt	1440
shale & lime	1760
lime	1895
lime & shale	2435
shale	2745
shale & lime	2960
lime	3155
shale	3250
lime	3500
shale, chert & lime	3540
shale & lime	3576
lime	3652
Total Depth	

TOPS:

Heebner	3100
Brown lime	3239
Lansing	3250
Conglomerate	3478
Viola	3494
Simpson shale	3510
Arbuckle	3563
DST #1: 3268-91, open 45 min. rec. 15' mud, BHP 235#	

DST #2: 3563-76, open 1 1/2 hrs. rec.
20' slightly O & G C mud, BHP 0#

DST #3: 3575-3605, open 75 min. rec.
15' slightly O & G C mud BHP 0#

DST #4: 3606-50, open 40 min. rec.
20' gas, 140' O & G C mud BHP 360#