


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANSCHUTZ DRILLING COMPANY
Farm- Christiansen No. 3

SEC. 15 T. 21 R. 12W
NE SW SE

Total Depth. 3635
Comm. 1-8-53 Comp. 1-20-53
Shot or Treated.
Contractor.
Issued. 12-5-53

County Stafford
KANSAS



Elevation. 1840 RB

Production. 42 B.O. / 65 wtr

Figures indicate Bottom of Formations.

sand	220
shale & shells	316
redbed	625
Anhydrite	650
shale	765
shale & shells	1315
shale	1440
lime & shale	1535
lime	1705
lime & shale	2180
shale & shells	2555
shale & lime	2735
lime	3090
shale	3095
lime	3155
shale & lime	3228
lime	3475
lime & shale	3480
Viola lime	3526
Simpson shale & Arbuckle	3575
Arbuckle	3635
Rotary Total depth	

Tops:	
Heebner	3090
Brown lime	3228
Lansing	3239
Cherty Conglomerate	3464
Viola chert	3480
Simpson shale	3524
Arbuckle	3578

Drill Stem Test's.
3264-3282, open 90", rec. 2160' gas, 30' ho&gcm, 30' vho&gcm, 30' vho & gcm & muddy oil, BHP 970#, closed 20".
3287-3322, open 1 hour, rec. 25' mud, BHP 780#, closed 20".
3360-3376, open 30", rec. 8' mud, BHP 0#, closed 15".
3394-3412, open 90", rec. 240' gas, 15' o&gcm, 25' watery mud, BHP 240#, closed 20".
3570-3585, open 90", rec. 480' gas, 60' ho&gcm & o&gcm, 5' wtr, BHP 0#, closed 20".