

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY WESTGATE-GREENLAND OIL COMPANY

SEC. 16 T. 21 R. 12W

FARM Williams

NO. 1

LOC. NW NE NW

TOTAL DEPTH 3536

COMM. 11-18-50


COMP. 11-29-50

COUNTY Stafford

SHOT OR TREATED

CONTRACTOR Jackson Drlg. Corporation

ISSUED 12-23-50



CASING

8 5/8" 298' cem. w/275 sx

ELEVATION 1846

PRODUCTION dry

FIGURES INDICATE BOTTOM OF FORMATIONS

sand w/clay & gravel	100
sand	220
sand & redbed	305
shale	400
redbed	500
redbed & shale	640
Anhydrite	683
shale & shells	1360
salt	1400
shale & shells	1460
lime & shale	1495
lime	1630
shale & lime	1845
lime	1980
shale & lime	2110
shale & shells	2130
lime	2180
shale	2204
shale & shells	2450
shale	2510
shale & shells	2560
lime	2590
lime with shale	2650
shale	2710
lime	2730
shale & lime	2840
lime	3125
shale & lime	3231
lime	3470
shale & lime	3498
Arbuckle	3536
Total depth	

Tops:

Anhydrite	640
Heebner	3080
Brown lime	3210
Lansing	3229
Arbuckle	3498

Drill stem test at 3536. Tool open 1 hr, rec. 75' mud and 120 feet salt water with sour gas.