


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- E. H. ADAIR OIL CO. & LEE PHILLIPS OIL
 Farm- Shumway No. 2 CO.

SEC. 27 T. 21 R. 12W
 SE NW NW

Total Depth. 3576
 Comm. 12-26-53 Comp. 1-3-53
 Shot or Treated.
 Contractor. E. H. Adair Oil
 Issued. 3-10-54

County Stafford
 KANSAS



CASING:
 8 5/8" 318 cem. w/200 sx.
 5 1/2" 3572 cem. w/100 sx.

Elevation. 1848 K.B.

Production. 95 bbls. * very
 slight show water

Figures Indicate Bottom of Formations.

sand	200 K.B.
shale red	318
shale	640
anhyd.	678
shale	1495
lime	1645
lime & shale	1934
lime	2220
shale & shells	2603
lime	2630
shale	2830
lime	3113
shale blk	3116
lime	3124
shale	3128
lime	3143
shale	3245
lime	3248
shale	3259
lime	3487
lime w/shale strks	3494
shale w/little chert	3497
chert	3516
shale	3564
shale w/thin strks of	
sand	3570
sand	3571
dolo.	3575
dolo.	3576
Total Depth	
Tops:	
Heebner	3113
Brown lime	3245
Lansing-K.C.	3259
Congl.	3594
Viola chert	3597
Simpson	3516
Arbuckle	3571

D.D. 3575-76 dolo. sft good
 sat, swb 3 BOPH