


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BEARDMORE, O. A. SUTTON & OIL TRADING SEC. 5 T. 21 R. 12W
 Farm- Sieker No. 1 ASSOC., INC. SE NE NW

Total Depth. 3510
 Comm. 4-12-53 Comp. 4-23-53
 Shot or Treated.
 Contractor. Beardmore Drlg. Co.
 Issued. 5-16-53

County Stafford
 KANSAS



CASING:
 8 5/8" 252' cem. w/135 sx

Elevation. 1851 DF

Production. Dry

Figures Indicate Bottom of Formations.

sand	220
shale, shells	252
red rock, shale,	
shells	655
anhydrite	675
shale, shells	1470
shale, lime	1610
lime broken	1820
lime	1955
lime, shale	2160
shale, shells	2300
shale, lime	3020
lime	3075
lime, shale	3195
lime	3510
Total Depth	

Tops:	
Heebner	3065
Brown Lime	3192
Lansing	3210
Arbuckle	3448

DST: #1 3214-3263' open
 1 hr. shut in 15 mins. rec.
 15' mud, BHP 0#. Weak blow
 throughout the hr.
 DST: #2 3449-3470' open 1 hr.
 shut in 15 mins. rec. 60' oil
 cut mud. BHP 450#.
 DST: #3 3470-3490' open 1 hr.
 20 mins. shut in 15 mins. rec.
 60' muddy wtr BHP 650#.