

8518-1

Stanolind #2 Fischer,  
SE SW SW, 3121S-12W.  
El. 1864'

Pennsylvanian conglomerate, 3543-3545'  
3543-3545, Rare sand. May be Misener or derived from Misener.

Viola residuum 3545-3580 35'  
3545-3580 White chert and rare red clay.

Decorah 3580-3623' 43'  
3580-3623 Green shales and rare sand. Streak of oilstained  
sand about 3610'

Arbuckle Top 3623' Penetration 9' Sub-sea, minus 17<sup>59</sup><sub>63</sub>'  
3623-3632 Dolomite, fine, brown. Presumably Upper Miller.

Both of these producers appear to be in the top  
of the Upper Miller but the samples alone do not  
show enough evidence to prove this. It is  
probable that there has been no compaction due  
to solution and that the actual top is the same  
as the restored top.