

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

3-21-13w

Company- CHIEF DRILLING CO., INC.
 Farm- McDonald No. 2

SEC. 3 T. 21 R. 13W
 NE NE SE

Total Depth. 3579'

Comm. 1-24-62


Comp. 2-5-62

Shot or Treated.

Contractor.

Issued. 10-13-62

County Stafford
 KANSAS



CASING:

8 5/8" 212' cem w/200 sx.

5 1/2" 3554' cem w/150 sx.

Elevation. 1874' DF

Production. 55 BOPD, 7% Wtr.

Figures Indicate Bottom of Formations.

sand & shale	212
shale & red bed	485
shale, shells & red bed	703
anhydrite	730
shale & shells	1530
shale & lime streaks	1555
lime	2175
shale & lime streaks	2338
shale & lime	2575
shale & lime streaks	2645
lime	2850
lime & shale	2950
lime	3121
lime & shale	3159
shale	3246
lime	3485
shale	3517
dolomite	3555
dolomite ?	3579
Total Depth	

TOPS:

Anhydrite	703
Heabner	3121
Toronto	3145
Douglas	3159
Brown Lime	3246
Lansing	3257
Base Kansas City	3485
Conglomerate	3497
Arbuckle	3517