

2-21-13W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - ARMER DRILG. CO., INC.  
Farm - Address No. 1

SEC. 2 T. 21 R. 13W  
NE NE NE SW

Total Depth. 3528 RTD  
Comm. 4-27-49 Comp. 5-12-49  
Shot or Treated.  
Contractor. Armer Drilg. Co. Inc.  
Issued. 7-16-49

County. Stafford  
KANSAS



Elevation. 1870 *ft*

Production. Pot. 242

CASING:

8 5/8" 197' cem. w/200 sx. cem.  
5 1/2" 3513' cem. w/125 sx cem.

Figures Indicate Bottom of Formations.

sand	120
shale & shells	192
iron & shale	197
surface clay & sand	250
red bed	540
red bed & shells	703
anhyd.	733
shale & shells	1575
lime	1580
shale & lime	1960
lime	1975
shale	2015
shale & shells	2245
shale & lime	2370
shale & shells	2500
shale	2655
shale & lime	3268
lime	3485
shale & lime	3509
shale	3512
Dolo.	3528
Total Depth	

Tops: Rot. bushing

Lansing-K. C.	3243
cherty congl.	3493
Simpson shale	3496
Simpson dolo.	3501
Simpson shale?	3504
Arb. dolo.	3512