

4-21-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PETROLEUM, INCORPORATED
Farm- FANSHIER "A" No. 2

SEC. 4 T. 21 R. 13W
SE NW NE

Total Depth. 3620'
Comm. 11-10-57 Comp. 11-22-57
Shot or Treated.
Contractor. GARVEY DRILLING COMPANY
Issued. 3-8-58

County Stafford
KANSAS



Elevation. 1887' DF

Production. 25 BOPD

CASING:
8 5/8" 255' cem w/225 sx
5 1/2" 3618' cem w/100 sx

Figures indicate Bottom of Formations.

surface sand & clay	125
hard sand	165
shale & sand	752
Anhydrite	767
shale & shells	1330
shale	1600
shale & shells	1685
lime	2025
shale & lime	2906
lime	3180
lime & shale	3286
lime	3501
lime & sand	3528
conglomerate	3568
Arbuckle	3620
Total Depth	

TOPS: SCOUT	
Anhydrite	752
Heebner	3153
Toronto	3170
Douglas Shale	3187
Brown Lime	3269
Lansing	3279
Conglomerate Sand	3510
Arbuckle	3567