

4- 21- 13W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- THE TEXAS COMPANY
Farm- C. D. Koopman No. 1

SEC. 4 T. 21 R. 13W
 NE NE SW

Total Depth. 3604 PBSD 3567
Comm. 5-16-55 Comp. 6-5-55
Shot or Treated.
Contractor, Prime Drilling Co.
Issued. 7-23-55

County Stafford
KANSAS



CASING:

10 3/4 @ 767' w/ 450 sx cmt.
7 in. @ 3603' w/ 100 sx cmt.

Elevation. 189' DF

Production Pmp. 79 BOPD, NW

Figures indicate Bottom of Formations.

surface clay	15
sand	135
shale, shells & red bed	757
anhydrite	795
shale & shells	1200
shale & lime	1620
lime	1795
lime & shale	1995
lime w/ shale breaks	2070
lime & shale	2285
lime w/ shale breaks	2385
shale & lime	2685
shale w/ lime streaks	2810
lime & shale	2970
lime w/ shale breaks	3035
lime	3205
lime & shale	3305
lime	3580
shale, lime, sand & chert	3586
Arbuckle lime	3591
lime	3604
Total Depth	

TOPS:

Topeka	2808
Heebner	3172
Toronto	3192
Brown lime	3291
Lansing	3303
Conglomerate	3523
Simpson	3533
/Arbuckle	3586