

10-21-13W


WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - MALLARD DRLG. & WESTGATE-GREENLAND
Farm - Ewalt No. 2

SEC. 10 T.21 R. 13W
CN/2 SE NE

Total Depth. 3553
Comm. 1-2-50 Comp. 1-21-50
Shot or Treated. Acid
Contractor. Mallard Drlg. Co.
Issued. 3-18-50

County. Stafford
KANSAS



Elevation. 1880 *ft*

CASING:
8 5/8" surface 290' cem. w/200 sx.
5 1/2" 3538' cem w/65 sx.

Production. Phys. Pot. 190 f
41

Figures Indicate Bottom of Formations.

surface sand	290
shale & shells	1600
lime	2140
lime & shale	2825
lime	3240
shale & lime	3267
Brown lime	3286
K. C. lime	3305
lime	3514
Simpson	3537
Arbuckle RTD	3540
Arbuckle, goodshow of oil	3547
Arbuckle	3553
Total Depth	

Tops:
Arbuckle 3537

MEASUREMENTS TAKEN FROM DERLICK FLOOR.

Acidized w/1000 gals. w/wtr & run tubing
and reacidized w/1500 gals.

Cardwell total depth 3547