

11-21-13W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - ATLANTIC REFG. COMPANY
Farm - McDonald No. 2

SEC. 11 T. 21 R. 13W
NW NW SW

Total Depth. 3518'
Comm. 3-11-49 Comp. 4-7-49
Shot or Treated. Acidized W/1500 gals.
Contractor. Loman-Johnson Drlg. Co.
Issued. 5-28-49

County. Stafford

KANSAS



CASING:
8-5/8" 266' Cem. W/225 Sx.
5-1/2" 3514' Cem. W/175 Sx.

Elevation. 1873 (2nd)

Production. 413 BO

Figures Indicate Bottom of Formations.

surface sand	71
sand & iron	101
iron & shale	130
shale & shells	305
red bed	728
anhydrite	759
shale	805
shale & shells	1190
shale & sand	1320
shale & lime	1350
shale	1555
lime & shale	1765
shale & lime	1930
lime	1980
lime & shale	2005
shale & shells	2265
lime & shale	2310
shale	2387
shale & lime	2480
shale	2588
shale & lime	2643
shale	2762
lime brkn	2842
lime	2890
shale	2912
lime & shale	3034
lime	3160
lime & shale	3270
lime	3457
lime & shale	3498
lime	3518
Total Depth	

Squeezed shale caving in re-worked
Arbuckle W/plastic. Drilled out
plastic. Drld. 1' of new hole.

Swabbed 22.5 BOPH thru tubing.
7% wtr - wat decreasing.

Tops:
Brown K. C. 3248
White K. C. 3266
Arbuckle 3512

Rotary T. D. 3517

Temporary allowable 25 BOPD
effective 4-7-49

State test 4-25-49 - 413 BO
daily allowable after state
test, 37 BOPD

Producing Area: 3514' to 3518'

Drilled plug. Filled up 150'
oil in 14 hrs. Ran Gamma Ray.