

sec. 13 - T21S - R13W

DRILLERS LOG

COMPANY:
CONTRACTOR:
LEASE NAME:
LOCATION:

ELEVATION:
SURFACE CASING:
OIL STRING:
COMMENCED:
COMPLETED:
ROTARY TOTAL DEPTH:

Aspen Drilling Co.
Aspen Drilling Co.
Batman #1
NW SW SW Sec.13-T21S-R13W
Stafford County, Kansas
1867' KB
6 jts.(241') 8 5/8"
122 jts.(3704') 5 1/2"
October 5, 1968
October 15, 1968
3700'

<u>FORMATION</u>	<u>DEPTH</u>
Sand	235
Shale	460
Red Bed & Sand	557
Shale & Sand	708
Anhydrite	734
Shale	1520
Shale-Lime	2725
Lime	3006
Lime-Shale	3090
Lime	3607
Arbuckle	3700

Prod. Oil
Ran 6 jts.(241') 8 5/8" casing se
at 249'. Cemented with 250 sacks
Cement Circulated.

DST #1 3290-3342
DST #2 3345-3364
DST #3 3398-3420
DST #4 3436-3484

Ran electric log.
Ran 122 jts.(3704') 5 1/2" set at
3698', cemented with 160 sacks.

<u>ELECTRIC LOG TOPS</u>	
Anhydrite	713
Heebner	3141
Toronto	3159
Douglas	3174
Brown Lime	3267
Lansing	3284
Base K. C.	3505
Conglomerate	3545
Simpson	3552
Arbuckle	3600
Log TD	3699

AFFIDAVIT

State of Kansas)
County of Barton) ss: