

16-21-13W


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - WESTGATE-GREENLAND OIL CO.
Farm - Grow No. 1

SEC. 16 T. 21 R. 13W
SW SW SE

Total Depth. 3709
Comm. 5-22-49 Comp. 6-26-49
Shot or Treated. Acid
Contractor. Jackson Drlg. Co.
Issued. 8-20-49

County. Stafford
KANSAS



Elevation. 1892 and

CASING:
8 5/8" 292' cem. w/275 sx. cem.
5 1/2" 3709' cem. w/75 sx. cem.

Production. 132 bbls. / 5%

Figures Indicate Bottom of Formations.

sand	90
iron & sand hrd	96
shale & shells	302
sand	400
red bed, shale, & shells	760
anhyd.	780
red bed & shale	1120
shale & shells	1600
lime	2030
shale & shells	2080
lime & shale	2260
lime	2295
shale & shells	2340
lime, shale	2445
shale & shells	2460
shale	2630
lime sdy.	2685
shale	2805
shale & shells	2905
lime	2975
lime & shale	3050
lime	3303
shale & lime	3350
lime	3537
lime rough	3621
shale	3642
lime & shale	3687
lime	3696
coring,reamed core hole	3701
Arbuckle	3709
Total Depth	

Tops:
Lime brn 3324
Lansing 3344
Arbuckle 3705

Acid Record:
1000 gals, Dowell Service. 2000 gals.
additional. 1000 gals additional. Lane-
Wells perforated 48 holed through casing
from 3705 to 3691.