

16-21-13W

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **WESTGATE GREENLAND OIL CO.**

SEC. 16 T. 21 R. 13W

FARM **Grow**


NO. 6

LOC. **NE SW SE**

TOTAL DEPTH **3660**
 COMM. **11-30-50**
 SHOT OR TREATED
 CONTRACTOR
 ISSUED **3-17-51**

COMP. **12-19-50**

COUNTY **Stafford**



CASING

8 5/8" 270' cem. w/225 sx & 2 CC
 5 1/2" 3660' cem. w/125 sx

ELEVATION **1890**

PRODUCTION **Pot. 186 BO NW**

FIGURES INDICATE BOTTOM OF FORMATIONS

soil and sand	60
sand	75
iron	87
shale & shells	270
rotton shale	315
sand	375
red bed w/shale	763
anhydrite	798
shale & shells	1172
shale & shells w/salt	1435
salt w/shale	1500
shale & shells	1610
lime	1910
lime w/shale	1960
lime	2010
lime w/shale	2050
lime	2063
lime	2175
lime w/ shale	2240
shale & shells	2290
lime & shale	2385
shale & shells	2630
lime & shale	3030
lime	3215
lime & shale	3320
lime	3570
lime w/shale & chert	3605
shale & cherty lime	3660
Total Depth D.F.	

All measurements taken from
 top of derrick floor.

DST: 3380-3399. Open 25 min.
 rec. 90' heavily oil cut mud
 & 450' free oil.

DST: 3444-3453. Open 1 hr rec.
 180' gas & 60' heavy oil & gas
 cut mud.

DST: 3463-3476. Open 45 min.
 rec. 2300' free oil.

Lane-Wells perforated 36 holes
 from 3662' to 3654'. 2 bbls.
 oil per hour.

1000 gals. Powell Service - 5
 bbls. oil per hr.

Tops:
 Brown Lime 3308
 Lansing 3322
 Viola 3562
 Simpson 3602
 Arbuckle 3644

Drill stem test 3352-3359.
 Open 1 hr - rec. 120' oil &
 gas cut mud, 120' salt water