

16-21-13W

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY WESTGATE GREENLAND OIL CO.

SEC. 16 T. 21 R. 13W
LOC. SE NW SE

FARM Grow NO. 7

TOTAL DEPTH 3662
COMM. 12-14-50 COMP. 1-17-51
SHOT OR TREATED
CONTRACTOR Jackson Drilling Corp. ✓
ISSUED 3-17-51

COUNTY Stafford
KANSAS



CASING

8 5/8" 286' cem. w/200 SX & 2 CC
5 1/2" 3656' cem. w/75 SX

ELEVATION 1892

PRODUCTION pot. 238 BO NW

FIGURES INDICATE BOTTOM OF FORMATIONS

soil and sand w/clay	71
iron	75
pyretic sand	88
shale & sand	245
shale & shells	288
shale & sand	345
sand	385
red bed w/shale	760
anhydrite	795
shale & shells	1245
shale	1390
salt w/shale	1475
shale & shells	1575
shale w/lime	1615
lime	1910
lime & shale	1940
lime	2225
lime & shale	2250
shale	2265
shale & lime	2325
shale & shells	2420
shale	2605
lime w/shale	3045
lime	3105
shale & lime	3230
lime	3235
shale & lime	3315
lime	3322
lime & shale	3325
lime	3570
lime w/chert	3611
shale & lime w/chert	3654
arbuckle	3662
Total Depth D.F.	

Tops;	
Anhydrite	760
Brown Lime	3318
Lansing	3334
Viola	3564
Simpson	3602
Arbuckle	3652

DST: 3361-3381. Open 1/2 hr
rec. 25' drilling mud with
very slight specks of free oil.
1000 gals. Dowell Service swabbing
5 bbls oil per hr.
All measurements from top of
derrick floor.